



Greenpiling

New Stadium – Rotherham United Football Club

Details

We negotiated with our client and the engineer to complete preliminary piling works to establish likely driven lengths prior to commencing the main piling works on site. The site was a large open space; however, the area where the West Stand of the building would be constructed was situated close to the railway line, therefore, we implemented the use of our smaller Viking piling rig to drive the piles in this area



Key Information

Duration	2 weeks	Number of piles	702 Piles
Rig	Junttan PM20	Pile Loads	Up to 550kN
Piling System	Steel Tube	Pile Lengths	Up to 14M
Ground conditions	Made Ground/ Soft Clay / Gravel/Mudstone	Testing Regime	Dynamic & Static

Contact Us

Smithy Brook Road
Renishaw
Sheffield
S21 3JS

Tel: 08450 511 800

Email: enquiries@greenpiling.co.uk

