



Greenpiling

Dunelm Offices – Syston

Details

Piles were installed over 9 days using a split piling platform. Only a limited site investigation was available prior to commencing on site therefore probe piles were first installed to finalise pile lengths which were agreed with the engineers based on the results and review of the data. As the design was based on a factory of safety of 3.0 static load testing was not required.



Key Information

Duration	3 Weeks	Number of piles	101 Piles total
Rig	Soilmec R312	Pile Loads	Up to 1600kN
Piling System	CFA	Pile Lengths	Up to 17m
Ground conditions	Made Ground/Sand/Silt/Gravel Mudstone	Testing Regime	Integrity

Contact Us

Smithy Brook Road
Renishaw
Sheffield
S21 3JS

Tel: 08450 511 800

Email: enquiries@greenpiling.co.uk

