



Greenpiling

New Mezzanine – Witherbush Retail Park- Haverfordwest

Details

The ground conditions of site was too dense for traditional mini piling so Green Piling proposed the use of BDSC as this was more cost effective and was achievable with a restricted headroom top driven rig. This enabled us to drive through dense cobbles in the ground. It was also suggested to dig out the cap prior to the piling works so cut off levels could be achieved immediately after driving and piles could be driven below ground level which minimised waste.



Key Information

Duration	3 Weeks	Number of piles	170 Piles
Rig	Viking	Pile Loads	270kN
Piling System	BDSC- Mini Piling	Pile Lengths	Up to 5M
Ground conditions	Made Ground/ Sand and Gravel/ Shale	Testing Regime	N/A

Contact Us

Smithy Brook Road
Renishaw
Sheffield
S21 3JS

Tel: 08450 511 800

Email: enquiries@greenpiling.co.uk

