



Bury M.B.C – Kirklees Bridge - Bury



Greenpiling

Details

Bury M.B.C hired Green Piling to install steel tubular piles for 2 No. bridge abutments for a new cycle bridge.

Both vertical and 1:3 raking piles were installed with pre-boring works to 12 no locations essential to allow installation of vertical piles due to the close proximity of the vertical face of the existing masonry abutment in relation to the proposed pile locations.



Key Information

Duration	2 weeks	Number of piles	24 Piles
Rig	Junttan PM20	Pile Loads	267kN
Piling System	Driven Steel Tube	Pile Lengths	Up to 13m
Ground conditions	Made Ground/Gravelly Clay/Clay & Gravel	Testing Regime	Dynamic Testing

Contact Us

Smithy Brook Road
Renishaw
Sheffield
S21 3JS

Tel: 08450 511 800

Email: enquiries@greenpiling.co.uk

