



Greenpiling

Horse Fen Bridge – North Thoresby

Details

Green Piling worked closely with the main contractor throughout the design stage to ensure the best piling system was chosen for the project. The site had a tight working space so prestart meetings with the client to place on site to ensure the best working practice was adopted to effectively use the space we had. The soils were not as firm as predicted so piles were driven deeper than anticipated but as a fixed price has been agreed there was no extra charge to the client.



Key Information

Duration	2 weeks	Number of piles	44 Piles
Rig	Juttan PM20	Pile Loads	Up to 580kN
Piling System	Driven Steel Tube	Pile Lengths	Up to 22m
Ground conditions	Clay	Testing Regime	Dynamic Testing

Contact Us

Smithy Brook Road
Renishaw
Sheffield
S21 3JS

Tel: 08450 511 800

Email: enquiries@greenpiling.co.uk

