



Greenpiling

A876- Upper Forth Crossing – Kincardine

Details

Green Piling undertook the installation of steel piles for a new bridge approach. Piles were installed over 3 separate Visits. The method & sequence was agreed between Green Piling and the Client to ensure works were completed on time and with reduced waste. The under piles were driven to 10-12m lengths before being welded to the appropriate extension pieces. Static testing was carried out before the extensions were added.



Key Information

Duration	Two Weeks	Number of piles	210 Piles
Rig	Junttan PM20	Pile Loads	Up to 1500kN
Piling System	Steel Tube	Pile Lengths	27M
Ground conditions	Made Ground/Alluvium/Glacial Till/Coal/Sandstone	Testing Regime	Kentledge/static

Contact Us

Smithy Brook Road
Renishaw
Sheffield
S21 3JS

Tel: 08450 511 800

Email: enquiries@greenpiling.co.uk

