



Greenpiling

## Cross Lane Hospital - Scarborough

### Details

Green Piling were sub-contracted to undertake the design and installation of CFA Piles for the redevelopment of Cross Lane Hospital. CFA piles were preferred due to the close proximity of other buildings and the works was within hospital grounds. Minor obstructions were encountered on site during installation however no delays occurred and the works were completed within the timescales required.



### Key Information

<b>Duration</b>	April –May 2010	<b>Number of piles</b>	129 Piles
<b>Rig</b>	Soilmec SF50	<b>Pile Loads</b>	Up to 225kN
<b>Piling System</b>	CFA	<b>Pile Lengths</b>	Up to 13m
<b>Ground conditions</b>	Made Ground/Boulder Clay/Mudstone	<b>Testing Regime</b>	Static & Integrity

# Contact Us

Smithy Brook Road  
Renishaw  
Sheffield  
S21 3JS

Tel: 08450 511 800

Email: [enquiries@greenpiling.co.uk](mailto:enquiries@greenpiling.co.uk)

