



Greenpiling

## Ideal Boilers – National Avenue - Hull

### Details

For the installation of over 1900 piles at Ideal Boilers in Hull we utilised our own precast concrete piles that are designed and manufactured directly at our manufacturing facility. We worked with Network Rail and the main contractor to ensure that piles were installed in accordance with safe working procedures including undertaking vibration monitoring.



### Key Information

<b>Duration</b>	Sept 2021–March 2022	<b>Number of piles</b>	1990 Piles
<b>Rig</b>	Junttan PM20	<b>Pile Loads</b>	450kN Compression
<b>Piling System</b>	Driven precast concrete	<b>Pile Lengths</b>	14-18M
<b>Ground conditions</b>	Tidal Flat Deposits, Overlying Burnham Chalk	<b>Testing Regime</b>	Dynamic Testing to 2.5% and 2no Static Load Tests.

# Contact Us

Smithy Brook Road  
Renishaw  
Sheffield  
S21 3JS

Tel: 08450 511 800

Email: [enquiries@greenpiling.co.uk](mailto:enquiries@greenpiling.co.uk)

