

## Industrial Units – Woodingdean Business Park - Brighton

## Details

This site previously housed a bakery, following demolition of this building, it was apparent that additional retaining walls were required to extend the basements onto the new building line. An agreed sequence of works was critical as both piling and excavation levels varied significantly across the site. Green Piling installed the main retaining wall plus two smaller retaining walls and bearing piles during a 4 week programme.



Greenpiling

## Key Information

Duration	3 Weeks
Rig	Soilmec 312
Piling System	CFA
Ground conditions	Chalk

Number of piles	140 Piles
Pile Loads	350kN
Pile Lengths	Up to 13M
Testing Regime	Integrity



Smithy Brook Road Renishaw Sheffield S21 3JS

Tel: 08450 511 800

Email: enquiries@greenpiling.co.uk













